## **ITEM 026000**

## Item 0260001 - 4'-4" ALUMINUM PEDESTAL Item 0260002 - 8' ALUMINUM PEDESTAL Item 0260003 - 12' ALUMINUM PEDESTAL

#### **DESCRIPTION**

This item shall consist of furnishing and installing a pedestal of the type and size specified on a prepared foundation at locations and to the details shown on the plans, or as ordered, and in accordance with these specifications.

#### **REFERENCED ITEMS**

None

## **REQUIRED SUBMITTAL**

Material Certificate of Compliance:

Submit 5 copies of material certificate of compliance for pedestals in accordance with the contract general requirements.

Certified Test Report:

Submit 5 copies of certified test reports for pedestals in accordance with the contract general requirements.

Shop Drawings:

Submit 5 copies of shop drawings for pedestals in accordance with the contract general requirements.

#### **MATERIALS**

The materials for this work shall conform to the requirements of Article M.16.03 of The State of Connecticut, Department of Transportation, Standard specification for Roads Bridges and Incidental Construction, Form 816, 2004.

#### **CONSTRUCTION METHODS**

The complete unit shall be erected vertically, mounted plumb, and shall be securely bolted to the foundation. All pedestals shall be effectively grounded using a 5/8-inch by 10-foot copper ground rod with #8 AWG solid, bare, tinned copper wire

attached to the pedestal by a stainless steel bolt and to the ground rod by a square head bolt clamp.

# **METHOD OF MEASUREMENT**

This work will be measured for payment by the number and type of pedestals specified, completed and accepted in place.

## **BASIS OF PAYMENT**

This work will be paid for at the contract unit price each for "(SIZE) ALUMINUM PEDESTAL", which price shall include all materials, pedestal base, shaft, ground wire, labor, tools, equipment, miscellaneous fittings and work incidental thereto.

PAY ITEM	<b>DESCRIPTION</b>	PAY UNIT
0260001	4'-4" Aluminum Pedestal	EA
0260002	8' Aluminum Pedestal	EA
0260003	12' Aluminum Pedestal	EA